

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00002 Page 0092

For corners in

Alpena (County)	Located in:	Corner Code #
1. Public Land Survey	T 32N R 05E	A13 ✓
	T 32N R 04E	H13
	T 31N R 04E	A01
	T 31N R 05E	H01
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

STATE OF MICHIGAN
County of Alpena
Recorded
08-25-1997 12:00:46
Kathy J. Natash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on April 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: Butler Ives, D.S. Found corner. Witnesses given: Hemlock 24 N 69° E 8, Dead Hemlock 24 S 45° W 13
- 1913: J. McNeil & W. Leroy Found 1-1/2" gas pipe. No witnesses given.
- 1973: Porter Survey Found 1/2" rod w/cap #18654. Witnesses given: S 45° W 49.20' Fence Corner, N 10° E 24.57' 6" Spruce, S 50° E 55.39' Fence Corner.
- 1989: R.S. Scott & Assoc. Found rod. Witnesses given: S 45° W 46.00' Fence Post, N 55° W 43.55' 8" Poplar, N 45° E 42.70' Fence Post, North 29.37' Fence Corner.
- Thomas L. Fabis, P.S. Found 1/2" iron rod. No witnesses given.
- 1994: Fred J. King, P.S. Set Montmorency County Remonumentation cap on found 1/2" rod. See witnesses given on LCRC form recorded in Liber 12, page 82, Montmorency County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found concrete monument with 1/2" rod with red plastic lining from remonumentation cap, 6" below road surface. Concrete monument is 8' North of Centerline of E/W road and 5' West of Centerline of road to the South.

SURVEY &
REMONUMENTATION

JUL 30 1999

SECTION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/11/97

Out B. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing concrete monument, 6" below road surface.



- Witnesses given:
- N 03° W 24.45' Fence Post (Found Cap #22435)
 - N 45° E 39.15' Fence Post (Found Cap #22435)
 - N 50° W 41.25' 8" Bam (Found Cap #22435)
 - N 60° W 48.55' 8" Bam (Found Cap #25852)
 - N 45° W 50.35' Fence Post (Found Cap #22435)
 - S 60° W 75.65' Power Pole (Found Cap #25852)

Signed by *Wayne T. Lewis*
Surveyor's Michigan License No. 41922

Date August 21, 1997