

**SURVEY &
REMONUMENTATION**

FEB 03 1998

1997 Alpena County Remonumentation

**SECTION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

Liber **00002** Page **0100**

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 32N R 05E	B07
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
County of Alpena
Recorded
08-25-1997 12:02:09
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on March 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1856: Josiah Knauer Set post. Witnesses given: Hemlock 20 N 53° W 3-1/2, Cedar 7 S 7° E 13.
1904: William Leroy Set 3" square cedar stake. Witnesses given: Hemlock Stump 24 N 53° W 3-1/2, Down Cedar 8 S 7° E 13, Cedar Stump 18 N 38-1/2° E 33.
1983: Ronald Bischer, P.S. Set 1/2" rod & cap #15410, 33' South of fence line to the North. Recorded LCRC in Liber 1, page 156, as M-7, but should be B-7. Witnesses given: N 43° W 46.37' Fence Post, N 24° W 36.37' Fence Post, N 08° E 33.25' Fence Post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Set 1/2" rered next to found 1/2" rered that was bent over.

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/1/97

[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" rered, 6" below road surface.



Witnesses given:
N 45° W 46.87' Fence Post (found tag #15410)
N 05° E 59.57' 7" Elm
N 08° E 33.80' Fence Post
N 30° W 41.45' Fence Post

Signed by *Wayne T. Lewis*
Surveyor's Michigan License No. 41922

Date August 21, 1997