

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Liber **00002** Page **0091**

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 32N R 05E T 31N R 05E T _____ R _____ T _____ R _____	<u>B13</u> B01 _____ _____
2. Property Controlling In Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

STATE OF MICHIGAN  
County of Alpena  
Recorded:  
08-25-1997 12:00:37  
Kathy J. Matash  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wayne T. Lewis, in a field survey on April 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: Butler Ives, D.S. Set Post. Witnesses given: Dead Cedar 10 N 61° E 30, Dead Spruce 7 S 12° W 12.
- 1913: J. McNeil & W. Leroy Set 1-1/2" gas pipe. No witnesses given.
- 1989: R.S. Scott Assocs. Set 1/2" rod. Witnesses given: S 30° E 38.9' Fence Post, South 34.5' Corner Fence Post, North 31.65' Corner Fence Post, N 50° E 60.35' Twin 3" Spruce.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Set 1/2" rod 2' North of road centerline using R.S. Scott witnesses. Rod is in line with fences to the North and South. Found Guthrie caps as described in other two Scott witnesses, but fence posts were leaning and not reliable.

SURVEY &  
REMONUMENTATION

JUL 30 1999

SECTION

P.A. 345 ALPENA COUNTY  
PEER APPROVED 6/19/97  
*D.P.R. Coon*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" rerod, 6" below road surface.



- Witnesses given:
- North 31.65' Fence Post (Found Cap #22435)
  - N 50° E 60.35' 4" Twin Spruce (Found Cap #22435)
  - S 08° E 65.67' 6" Ash
  - S 40° E 84.01' 6" Aspen

Signed by *Wayne T. Lewis*  
Surveyor's Michigan License No. 41922

Date August 21, 1997