

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00002 Page 0103

For corners in

Alpena (County)	Located In:	Corner Code #
1. Public Land Survey	T 32N R 05E	005
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property In Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
County of Alpena
Recorded
08-25-1997 12:02:39
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Wayne T. Lewis, in a field survey on March 7, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer Set post. Witnesses given: Fir 6 S 10° W 14, Cedar 8 N 35° E 24.
- 1906: William Leroy Found original corner. Set 3" square cedar stake. Witnesses given: Down Cedar 14 N 37° W 19, Down Hemlock 16 S 42° E 19, Cedar 15 N 60° W 23.
- 1918: William Leroy Found 4" square cedar stake. Witnesses given: Cedar 15 N 60° W 23.
- 1941: William Leroy Found 3" square cedar stake. No witnesses given.
- 1983: Ronald Bischer, P.S. Found 1" pipe. Ronald Bischer recorded LCRC in Liber 1, page 160. Witnesses given: N 85° W 31.63' Fence Corner, N 87° E 32.44' Fence Corner, N 45° E 62.69' 6" Balsam.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Set 1/2" rerod inside found 2" pipe, 2' West of road centerline.

SURVEY &
REMONUMENTATION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/1/97

[Signature]

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" rerod, 6" below road surface.



Witnesses given:

- S 88° W 31.70' Fence Post
- S 85° W 28.40' 5" Ash
- N 85° W 32.87' Fence Post (found tag #22435)
- S 30° E 64.78' 6" Balsam
- N 45° E 62.70' 6" Balsam Stump (found tag #15410)
- N 45° E 63.20' 8" Cedar

Signed by *[Signature]*
Surveyor's Michigan License No. 41922

Date August 21, 1997