

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00002 Page 0104

For corners in

Alpena (County)	Located In:	Corner Code #
1. Public Land Survey	T 32N R 05E	C06
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
County of Alpena
Recorded
08-25-1997 12:02:47
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on March 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer Set Post. Witnesses given: Hemlock 10 S 63° E 16, Hemlock 30 N 63° W 12.
- 1900: William Leroy Found corner. Set 3" square cedar stake. Witnesses given: Down Hemlock 10 S 60° E 16, Down Hemlock 30 N 35° W 12, White Pine Stump 30 N 35° W 32.
- 1906: William Leroy No monumentation given. Witnesses given: White Pine Stump 30 N 35° W 32.
- 1980: R.S. Scott Assocs. Found concrete monument as recorded in Liber 1, page 980-981 of Certificates of Survey. Witnesses given: S 80° W 34.48' 10" White Pine, S 40° W 56.35' 16" Maple, N 45° E 44.39' Fence Post.
- 1983: Ronald Bischer, P.S. Found 3" square concrete monument & 3 old witness tags #22435, raised with 1/2" rod and cap #15410. Witnesses given: N 58° E 44.34' Gate Post, S 84° W 34.54' 14" Norway, S 40° W 56.82' 16" Maple.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found 1/2" rerod.

SURVEY &
REMONUMENTATION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/1/97

D.P.B. Cur

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rerod, 6" below road surface.



Witnesses given:
N 85° E 33.74' Gate Post (found tag #22435 in face)
S 85° W 34.35' 16" Red Pine
S 40° W 56.60' 20" Maple
S 15° E 34.25' 30" Willow

Signed by Wayne T. Lewis
Surveyor's Michigan License No. 41922

Date August 21, 1997