

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00002 Page 0105

For corners in

Alpena (County)	Located in:	Corner Code #
1. Public Land Survey	T 32N R 05E	C07
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
County of Alpena
Recorded
08-25-1997 12:02:55
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Wayne T. Lewis, in a field survey on March 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer Set post. Witnesses given: Hemlock 16 N 72° W 12, Hemlock 16 S 33° E 34.
- 1904: William Leroy Found old post. Set 4" square cedar stake. Witnesses given: B Ash 14 N 7° E 77-1/2.
- 1906: William Leroy Found 4" square cedar stake. Witnesses given: B Ash 14 N 7° E 77-1/2, Cedar Stake 3" N 41° 30' W 70.
- 1974: R.S. Scott Assocs. Found 1/2" rod. Witnesses given: N 45° E 67.27' Power Pole, N 20° E 75.28' 12" Maple, N 45° W 66.15' 4" Poplar.
- 1980: R.S. Scott Assocs. Found concrete monument as recorded in Liber 1, page 980-981 of Certificates of Survey. Wit. given: S 45° E 51.28' Power Pole, N 45° E 67.23' P. Pole, S 30° W 90.00' P. Pole.
- 1983: Ronald Bischer, P.S. Found 6" square conc. mon. R. Bischer recorded LCRC in Liber 1, page 156, as B-7, but should be C-7. Wit. given: N 57° E 67.70' Power Pole, S 40° E 51.36' Anchor Pole, S 22° W 89.66' Anchor Pole.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found concrete monument.

SURVEY &
REMONUMENTATION

AUG 3 1997

SECTION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/1/97

D.P.B. Co.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing concrete monument, 6" below road surface.

Witnesses given:
N 57° E 62.27' Power Pole
N 20° E 76.25' 15" Maple
S 10° W 89.65' Anchor Pole (found tag)
S 10° E 102.50' Power Pole



Signed by Wayne T. Lewis
Surveyor's Michigan License No. 41922

Date August 21, 1997