

RECORDED ALPENA COUNTY MI.

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alpena County

OCT 12 2 12 PM '95

Kathy G. Matash REGISTER OF DEEDS

005756

Register of Deeds Stamp & File Number

Table with columns: Located In: (County), Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. Recorded Plat Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Earl T. Lewis, in a field survey on May 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: AUGUST 23, 1856: GLO Surveyor, Josiah Knauer set post, no monumentation given, witnesses given: Cedar 6 N 85° W 16, Balsam 6 N 35° E 12 AUGUST 14 1895: County Surveyor W. LeRoy, set cedar stake in place of old U.S. survey post. witnesses given: Cedar 6 N 85° W 17 (lying down), Tamarack 14 S 32° W 58 1/2, Tamarack 12 N 61 1/2° E 39 MAY 24, 1993: Earl T. Lewis, P.S. set 1/2" rerod, witnesses given: S 45° W 41.25' Power Pole, S 45° E 50.20' Power Pole, N 45° W 91.75' 20" Aspen, N 70° W 73.60' 10" Aspen AUGUST 10, 1994: THOMAS L. FABIS, P.S. found 1/2" iron rod, no witnesses given.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 1/2" rerod in intersection of Godfrey and Truax roads.

P.A. 345 ALPENA COUNTY PEER APPROVED 6/29/95 [Signature]

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 1995, Placed appropriately stamped Alpena County Remonumentation aluminum cap on existing rerod, 6" below road surface.

Witnesses:

- S 60° W 41.25' Power Pole (found nail) S 55° E 50.15' Power Pole (found nail) N 50° W 79.45' 6" Maple N 75° W 73.63' 14" Poplar (found remains of ribbon)



Signed by Earl T. Lewis Date October 8, 1995

Surveyor's Michigan License No. 27452