

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
ALPENA COUNTY MI.

Oct 12 2 12 PM '95

Kathryn M. Matush
REGISTER OF DEEDS

005758

Register of Deeds Stamp & File Number

For corners in
Alpena County

(County)

Located In:

Corner Code -#

- 1. Public Land Survey T 32N R 05E C-10
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Earl T. Lewis in a field survey on May 10, 1995
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
AUGUST 23, 1856: GLO Surveyor, Josiah Knauer set post, no monumentation given, witnesses given:
Sym 12 N 22° E 25
B. Ash 12 S 80° W 23
MAY 12 1894: County Surveyor W. LeRoy, found cedar stake, witnesses given:
B. Ash Stump 14 S 80° W 24 (ONBT)
Cedar stake 4 West 50
Cedar stake 4 East 50

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Set 1/2" rerod in intersection of Woodruff and Truax roads, and in line with an existing fence. The distances to Section corners to the North and South agree closely with county surveyor's notes.

P.A. 345 ALPENA COUNTY
PEER APPROVED 4/29/95
D. B. [Signature]

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1995, Placed appropriately stamped Alpena County Remonumentation aluminum cap on set 1/2" x 24" rerod, 6" below surface.

Witnesses:

- N 35° E 43.22' Power Pole
- N 60° W 37.23' 6" Spruce
- N 85° W 64.75' 5" Spruce
- N 35° E 72.65' 5" Spruce



Signed by Earl T. Lewis

Date October 8, 1995

Surveyor's Michigan License No. 27452