

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED ALPENA COUNTY MI.

OCT 12 2 13 PM '95

Kathryn M. Pease REGISTER OF DEEDS

005759

Register of Deeds Stamp & File Number

For corners in

Alpena County

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 32N R 05E C-11
2. Property Controlling in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Earl T. Lewis in a field survey on May 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column C and row 11.

- A. Description of original monument and accessories and/or subsequent restoration:
AUGUST 20, 1856: GLO Surveyor, Josiah Knauer set post, no monumentation given, witnesses given: B. Ash 4 S 62° E 26, Dead Pine 2 S 87° W 37
MAY 12 1894: County Surveyor W. LeRoy, set cedar stake, witnesses given: B. Ash 4 S 62° E 26, Dead Pine 2 S 87° W 37, Cedar stake 5 West 50, Cedar stake 4 East 50
AUGUST 16, 1895: County Surveyor W. LeRoy, found cedar stake, witnesses given: Same as above.
JUNE 16, 1915: County Surveyor W. LeRoy, found cedar stake, witnesses given: Same as above.
MARCH 04, 1974: Porter Survey, found 1/2" pipe, witnesses given: N 40° E 49.85' Black Ash, Due East 28.23' Fe. Corner

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found nail with washer in intersection of Doran and Truax roads, and in line with an existing fence.

P.A. 345 ALPENA COUNTY PEER APPROVED

Handwritten signature and date 10/29/95

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 1995, Placed appropriately stamped Alpena County Remonumentation aluminum cap on set 1/2" x 24" rerod, which was set in place of existing nail.

Witnesses:

- N 35° E 50.85' 20" Ash
N 25° E 29.60' Power Pole
S 85° E 34.53' 12" Ash
N 85° E 27.30' Fe. Corner
S 35° E 57.75' 12" Poplar
S 40° W 61.27' 15" Red Pine



Signed by Earl T. Lewis

Date October 8, 1995

Surveyor's Michigan License No. 27452