

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

OCT 12 2 13 PM '95

Kathy M. Matash REGISTER OF DEEDS

005760

Register of Deeds Stamp & File Number

For corners in Alpena County (County)

Located In: Corner Code #

- 1. Public Land Survey T 32N R 05E C-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, Earl T. Lewis, in a field survey on May 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-12. Cell (12, C) contains a dot.

- A. Description of original monument and accessories and/or subsequent restoration:
AUGUST 20, 1856: GLO Surveyor, Josiah Knauer set post, no monumentation given, witnesses given: Hemlock 4 N 49° W 5, Norway Pine 30 S 35° E 13
AUGUST 16, 1895: County Surveyor W. LeRoy, reestablished corner, set cedar stake, witnesses given: Down W. Pine 30 S 35° E 13, W. Pine 28 S 64° W 45 1/2
MAY 10, 1912: County Surveyor W. LeRoy, and County Surveyor Jos. McNeil found corner established by W. LeRoy, no monumentation given, no witnesses given.
MARCH 04, 1974: Porter Survey, found railroad spike, witnesses given: S 30° W 48.81' 22" Norway, N 20° E 52.22' 8" Tamarack, S 85° E 59.51' J. Pine

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found railroad spike in center line of Truax Road, and in line with an existing fence.

P.A. 345 ALPENA COUNTY PEER APPROVED 6/29/95 [Signature]

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 1995, Placed appropriately stamped Alpena County Remonumentation aluminum cap on set 1/2" x 24" rerod, which was set in place of railroad spike.

- Witnesses:
N 70° E 30.70' Power Pole
S 75° E 49.87' 6" Tamarack
S 70° W 38.05' 8" Maple
N 50° W 42.70' 24" Red Pine



Signed by Earl T. Lewis Date October 8, 1995

Surveyor's Michigan License No. 27452