

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Liber 00002 Page 0094

Alpena (County) Located in: Corner Code #

1. Public Land Survey T 32N R 05E G13
T 31N R 05E G01
T R
T R
T R

2. Property Controlling in Section S T R
S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
County of Alpena
Recorded
08-25-1997 12:01:10
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Wayne T. Lewis, in a field survey on March 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: Butler Ives, D.S. Set post. Witnesses given: Dead Ash 10 N 10° W 7, Dead Ash 12 N 81° E 22.
- 1913: J. McNeil & W. Leroy Set 2" gas pipe in North edge of road bed 20 links East of large ditch or culvert. No wit. given.
- 1976: R.S. Scott Assocs. Set 1/2" rod. Witnesses given: S 35° E 53.00' 6" Elm, N 10° W 51.90' 8" Elm, N 50° E 74.20' 14" Maple.
- 1990: Thomas L. Fabis, P.S. Set 1/2" rod 10' North of road centerline by proportionate method using F-13 and H-13, referring to 1913 notes from Joseph W. McNeil. Thomas L. Fabis recorded corner in Liber 1, page 222.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found 1/2" rerod w/undentifiable cap. Also found 1/2" rerod S 54° 46' 37" E 16.88' from capped rod.

SURVEY & REMONUMENTATION

AUG 30 1999

SECTION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/1/97

D.P.A. Loh

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing rerod, 6" below road surface.



- Witnesses given:
- N 55° E 51.95' 7" Ash (found nail & tag #31591, set tag #41922)
 - N 44° W 64.67' 7" Ash (found nail & tag #31591, set tag #41922)
 - S 52° W 57.77' 6" Maple (found blaze)
 - S 40° E 77.55' 7" Ash (found blaze)
 - West 18.00' Centerline of culvert

Signed by *Wayne T. Lewis*
Surveyor's Michigan License No. 41922

Date August 21, 1997