

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Liber 00002 Page 0097

Alpena (County) Located In: Corner Code #

1. Public Land Survey T 32N R 05E 113
T 31N R 05E 101
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property In Sec. S T R

STATE OF MICHIGAN
County of Alpena
Recorded
08-25-1997 12:01:42
Kathy J. Natash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on March 6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: Butler Ives, D.S. Set Post. Witnesses given: Dead Hemlock 12 N 32° W 3, Dead Hemlock 8 N 61° E 15.
- 1913: J. McNeil & W. Leroy Set 2" gas pipe. No witnesses given.
- 1976: R.S. Scott Assocs. Set 1/2" rod. Witnesses given: N 05° E 35.16' Power Pole, S 60° W 68.10' 16" Poplar, S 45° E 63.00' 10" Spruce.
- 1990: Thomas L. Fabis, P.S. Found 2" gas pipe. Witnesses given: N 16° E 56.25' 6" Ash, N 35° W 62.78' 8" Maple, S 16° W 49.68' 12" Spruce, S 52° E 80.34' 9" Ash.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Set 1/2" rod using witnesses from Thomas L. Fabis, P.S. Found orange ribbon, but no evidence of a pipe.

SURVEY & REMONUMENTATION

AUG 30 1997

SECTION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/1/97
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" rered, 6" below road surface.



- Witnesses given:
- N 16° E 56.25' 6" Ash (found tag #31591)
 - N 35° W 62.78' 8" Maple Stump (found tag #31591)
 - S 16° W 49.68' 12" Spruce (found tag #31591)
 - S 52° E 80.55' 9" Ash (found tag #31591)
 - N 60° W 57.30' Power Pole

Signed by *[Signature]*
Surveyor's Michigan License No. 41922

Date August 21, 1997