

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970 Liber 00002 Page 0098

For corners in

Alpena Located In: Corner Code #  
 (County)

1. Public Land Survey T 32N R 05E J13  
 T 31N R 05E J01  
 T R  
 T R  
 T R

2. Property Controlling in Section S T R  
 S T R  
 S T R

3. Miscellaneous Property in Sec. S T R  
 S T R

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 County of Alpena  
 Recorded:  
 08-25-1997 12:01:51  
 Kathy J. Matash  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wayne T. Lewis, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1855: Butler Ives, D.S. Set post. Witnesses given: Dead Cedar 12 N 8° E 24, Dead Cedar 8 S 15° W 17.  
 1913: J. McNeil & W. Leroy Set cedar stake. No witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1997: Set 1/2" rod, by single proration, 2' South of road centerline (midway and on line between I-13 & K-13). Found wire going to the North, 35' West.

SURVEY &  
 REMONUMENTATION  
 SECTION

P.A. 345 ALPENA COUNTY  
 PEER APPROVED 5/1/97  
*[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" rerod, 6" below road surface.



Witnesses given:  
 N 15° W 41.20' Power Pole  
 S 10° E 109.12' Power Pole  
 N 25° E 64.75' 10" Spruce  
 S 10° W 54.02' 4" Ash

Signed by Wayne T. Lewis  
 Surveyor's Michigan License No. 41922

Date August 21, 1997