

**SURVEY &
REMONUMENTATION**

NOV 16 1998

1998 Alpena County Remonumentation

Liber **00002** Page **0167**

SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey

T 32NR 06E

A-7

T 32NR 05E

M-7

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
County of Alpena
Recorded
10-08-1998 09:57:36
Kathy J. Matach
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Wayne T. Lewis, in a field survey on 5-19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1857: GLO, Josiah Knauer, D.S. - found old post & witnessed
- 1889: William H. Leroy, C.S. - found corner
- 1902: William H. Leroy, C.S. - set new 2" square cedar stake in place of old one & witnessed
- 1915: Joseph W. McNeil, C.S. - set new stake in place of old one
- 1976: David B. Guthrie, P.S. - set railroad spike and recorded in Liber 1 of Surveys, pages 326 & 327, & witnessed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998: Found railroad spike 1.5' below road surface; corner is in line with C/L of road North and South, and in C/L of road to the West. Set 1/2" rerod next to railroad spike.

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED *[Signature]*

[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: Placed 3" Alpena County cap, stamped to identify the corner, on existing rerod, 6" below road surface.

Witnesses:

- S 85° W 81.40' 30" Clump of Maple
- N 10° E 138.67' Power Pole
- S 05° E 129.88' Most N'ly guard post on East side of bridge
- S 05° W 129.51' Most N'ly guard post on West side of bridge



Signed by *[Signature]*
Surveyor's Michigan License No. 41922

Date September 19, 1998