

1994
 APR 08 1994
 SURVEY & REMONUMENTATION COMMISSION

1994 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Dec 8 10 10 AM '94

REGISTER OF DEEDS

For corners in Alpena (County) Located In: Corner Code #

1. Public Land Survey	T <u>32N</u> R <u>6E</u>	<u>E-6 (W$\frac{1}{2}$, 16)</u>
	T _____ R _____	<u>Long Rapids Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas L. Fabis, in a field survey on May 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1856: G.L.O. Resurvey by Josiah Knauer - set post & referenced: (Hemlock 12 - S84°E - 6 lks, Hemlock 8 - N75°W - 19 lks)
 - 1901: County Survey by Wm. H. LeRoy - Set 3" sq. cedar stake in road & referenced.
 - 1992: Recorded Survey by Earl T. Lewis - Set R.R. spike by proportionate method using 1901 county survey measurements for reference.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994: Found R.R. Spike 5' East of centerline of Leer Road and one witness as per 1992 recorded survey by Earl T. Lewis (Liber 2 Page 696). This corner position is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1994: Removed existing corner material and set $\frac{1}{2}$ " iron rod with 3" dia. aluminum cap, stamped to identify the corner, inside a Monument Box.
 Reestablished witnesses are:
 Set tag #31591 in P. Pole - N35°E - 42.60'
 Set tag #31591 in 6" Apple - S40°E - 53.20'
 Set tag #31591 in 3" Cedar - West - 41.85'
 Exis. tag in 8" W. Pine - N36°E - 71.94'

RA. S45 ALPENA COUNTY
 PEER APPROVED Nov. 10, 1994
D. B. Tuttle

Signed by Thomas L. Fabis Date Dec. 5, 1994
 Surveyor's Michigan License No. 31591

