

1994 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

DEC 8 10 11 AM '94

REGISTER OF DEEDS

For corners in

Alpena

(County)

Located In:

Corner Code: #

- 1. Public Land Survey T 32N R 6E E-8 (W 1/4, 21) Long Rapids Twp.
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, Thomas L. Fabis, in a field survey on May 25, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 8.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1856: G.L.O. Resurvey by Josiah Knauer - set post & referenced: (Hemlock 18 - S55°E - 14 lks., Hemlock 9 - N37°W - 13 lks.)
1893: County Survey by Wm. H. LeRoy - Measured to corner from 1/2 mile South.
1916: County Survey by Jos. W. McNeil - drove gas pipe beside large stone.
1976: Survey by David B. Guthrie - set R.R. spike and referenced.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994: Found R.R. spike and two witnesses (West - 46.19' - Anchor Pole, S50°W - 64.46' - P. Pole) as per David B. Guthrie Survey of 1976. This corner position is compatible with County and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

SURVEY & REMONUMENTATION

JUL 30 1993

SECTION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1994: Removed existing corner material and set 1/2" iron rod with 3" dia. aluminum cap, stamped to identify the corner, inside a Monument Box.

Reestablished witnesses are:
Exis. roofing nail in P. Pole - S50°W - 64.46'
Exis. roofing nail in Anchor Pole - West - 46.19'
Set tag #31591 in Anchor Pole - N80°E - 31.00'
Set tag #31591 in 6" Apple - N30°W - 79.53'

P.A. 345 ALPENA COUNTY PEER APPROVED Oct. 27, 1994

Signed by Thomas L. Fabis Date Dec. 5, 1994

Surveyor's Michigan License No. 31591

