

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located in:

Corner Code #

1. Public Land Survey

T32NR 06E

G-1 ✓

T33NR 06E

G-13

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

ALPENA COUNTY &  
REMONUMENTATION

JAN 21 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Wayne T. Lewis, in a field survey on 6-01, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer found post and witnessed
- 1896: Wm. H. Leroy set Cedar stake, 5" square, and witnessed
- 1905: J. McNeil found cross line in East edge of road, did not find stake, no monumentation or witnesses given
- 1918: J. McNeil found large Cedar stake, no monumentation or witnesses given
- 1962: G. Wozniak, MDOT Surveyor, found 1-1/4" pipe in mon. box 1.32' rt. of M-65 C/L.
- 1991: T. Fabis, P.S., found 1" pipe in mon. box and recorded corner in Liber 1, Page 230

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/4" pipe in mon. box, 1' East of M-65 C/L., and 4' North of Kensa Road C/L

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY  
PEER APPROVED 9/16/99  
*D. J. R. K.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County Cap, stamped to identify the corner, on 1/2" rerod driven inside pipe

Witnesses:

- N 80° E 64.52' Set Chis. Notch in North End of 36" CMP
- S 76° E 78.15' Power Pole (Fd. Fabis Tag)
- S 60° W 69.33' "+" in 55+57 Stationing Stamped in Headwall
- N 78° E 65.87' "+" in Con. Headwall



Signed by *Wayne T. Lewis*  
Surveyor's Michigan License No. 41922

Date November 24, 1999