

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Alpena  
(County)

Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 32NR 06E G-2  
T \_\_\_\_\_  
T \_\_\_\_\_  
T \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_  
in Section S \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_

REGISTERED

JAN 21 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Wayne T. Lewis, in a field survey on 6-01, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4	●	3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer found post and witnessed
- 1896: Wm. H. Leroy set Cedar stake, 6" square, and witnessed
- 1962: G. Wozniak, MDOT Surveyor, found 1-1/4" pipe in mon. box in C/L of M-65
- 1991: T. Fabis, P.S., found 1" pipe in mon. box, recorded survey (L2, P582) and LCRC (L1, P230) and witnessed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/4" pipe in mon. box, in M-65 C/L, and 14' South of Zajkowski Rd.

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY  
PEER APPROVED 9-16-99  
*D. B. [Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County Cap, stamped to identify the corner, on 1/2" rerod driven inside pipe

Witnesses:

- N 60° E 87.55' Power Pole (Fd. Fabis Tag)
- N 64° E 80.11' ROW Marker
- S 75° E 61.06' Cor. Fe. Post (Fd. Fabis Tag)
- S 89° W 57.22' 8" Ash
- S 58° E 67.72' ROW Marker
- S 89° W 60.25' Broken R/W Marker



Signed by [Signature]  
Surveyor's Michigan License No. 41922

Date November 24, 1999