

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>32</u> NR <u>06</u> E	<u>G-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED

JAN 21 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 6-01, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3			2		1
3													
4	7		8			9		10			11		12
5													
6	18		17			16		15			14		13
7													
8	19		20			21		22			23		24
9													
10	30		29			28		27			26		25
11													
12	31		32			33		34			35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer reestablished old post and witnessed
- 1889: Wm. H. Leroy found stake, set new cedar stake, no witnesses given
- 1896: Wm. H. Leroy found stake, no witnesses given
- 1896: Wm. H. Leroy found point of old stake, set new stake 4" square, and witnessed
- 1912: J. McNeil found corner set by Leroy, no witnesses given
- 1962: G. Wozniak, MDOT Surveyor, found 1-1/4" pipe in mon. box, 1.31' rt. of M-65 C/L, and witnessed
- 1978: E. D. Farrier, P.S., fd 1" pipe in mon box, 1' E. of M-65 C/L, recorded survey (L1, P734) & LCRC (L1, P102), and witnessed
- 1989: E. T. Lewis, P.S., used corner, no monumentation or witnesses given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/4" pipe in mon. box, 1.2' East of M-65 C/L, and on Maple Lane Rd. C/L
Fits both Poplar witnesses from Farrier, but too overgrown to use

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99
D.P.A. L

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County Cap, stamped to identify the corner, on 1/2" rerod driven inside pipe

Witnesses:

- N 87° E 179.18' W Corner of Cable Riser
- N 87° E 180.40' Filed Notch in Angle Iron Fence Post
- S 74° W 73.85' 10" Birch
- S 45° W 42.43' Set 1/2" Rerod w/cap
- N 45° W 75.00' 9" Poplar



Signed by *Wayne T. Lewis*
Surveyor's Michigan License No. 41922

Date November 24, 1999



L- 2 P- 245
11/30/1999 03:30P
Page: 1 of 1