

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---|------------------|------------|
| 1. Public Land Survey | T | <u>T32NR 06E</u> | <u>G-5</u> |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

REGISTERED

JAN 21 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 6-01, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer set old post and witnessed
- 1896: Wm. H. Leroy reestablished old corner, set new stake, 4" square, and witnessed
- 1917: Wm. H. Leroy replaced stake with blue granite stone, and witnessed
- 1900: J. McNeil found corner set by Leroy, no witnesses given
- 1962: G. Wozniak, MDOT Surveyor, found 1-1/4" pipe in mon. box 3.13' ft. of M-65 C/L.
- 1978: E. D. Farrier, P.S., fd 1" pipe in mon box, 1' N. of C/L E., 1' N. of fe. W., and 3' W. of M-65 C/L, recorded LCRC (L1, P102)
- 1982 and 1989: E. T. Lewis, P.S., found mon. box, and witnessed
- 1997: W. T. Lewis, P.S., found 1" pipe in mon. box, and witnessed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/4" pipe in mon. box, 3.5' East of M-65 C/L, and 3' South of Johnson Rd C/L

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.


P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99
W. T. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County Cap, stamped to identify the corner, on 1/2" rerod driven inside pipe

Witnesses:

- S 85° E 60.75' Chis. "X" in South End Conc. Culv.
- N 60° E 116.90' Power Pole (Fd. Tag #41922)
- N 50° W 35.22' Chis. "X" in North End Conc. Culv.
- N 30° W 183.63' Power Pole (Fd. Tag #41922)
- S 30° W 187.94' Power Pole (Fd. Tag #41922)
- S 50° W 39.28' Chis. "X" in S End of Conc. Culv.




Signed by

Wayne T. Lewis

Date November 24, 1999

Surveyor's Michigan License No. 41922



L-2 P-247
11/30/1999 03:30P
Page: 1 of 1
Kathy J. Matash, Register Alpena Co., MI LDC 9.00

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1996