

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey

T32NR.06E

G-7

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

REGISTERED

JAN 21 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 6-01, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer reestablished old post and witnessed
- 1893: F. A. Rice found old stake, set Cedar stake 5" square with crockery and glass at bottom
- 1896: Wm. H. Leroy found stake 4" square, and witnessed
- 1901: Wm. H. Leroy reestablished old corner, set blue boulder, and witnessed
- 1962: G. Wozniak, MDOT Surveyor, found 1-1/4" pipe in mon. box 7.42' lt. of M-65 C/L, and witnessed
- 1973: E. LaCross, P.S., found monument, no witnesses given
- 1974: J. Scott, P.S., found mon. box, recorded LCRC (L1, P41-42), no witnesses given
- 1976: R.S. Scott (D. B. Guthrie, P.S.) from field notes, found mon. box, used witnesses from MDOT records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe in mon. box, 9' West of M-65 C/L, in Greenwood Rd. C/L

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99

J.D.R. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County Cap, stamped to identify the corner, on 1/2" rerod driven inside pipe

Witnesses:

- S 45° E 59.10' Chis. "X" in North End Conc Headwall
- S 35° W 43.89' Set Chis. "X" in Conc. Headwall
- N 70° W 66.40' 22" Maple
- N 45° W 100.70' 24" Spruce



Signed by [Signature]
Surveyor's Michigan License No. 41922

Date November 24, 1999