

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey

T 32 N R 06E

G-9

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____

T _____ R _____

S _____

T _____ R _____

3. Miscellaneous
Property in Sec.

S _____

T _____ R _____

S _____

T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 6-01, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer set post and witnessed
- 1893: F. A. Rice and Wm. H. Leroy found old stake and set boulder for corner, and witnessed
- 1962: G. Wozniak, MDOT Surveyor, found 1-1/4" pipe lt. of Hwy. M-65, in Thorne Rd., and witnessed
- 1976: R. S. Scott (D. B. Guthrie, P.S.) set R.R. spike, and witnessed
- 1998: T. L. Fabis, P.S., found boat spike in mon. box, and witnessed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike in mon. box 48' West of M-65 C/L, and in Thorne Rd. C/L
Found good dip 51.9' East of corner in Thorne Road C/L and on M-65 tangent

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County Cap, stamped to identify the corner, on 1/2" rerod driven next to boat spike

Witnesses:

- S 35° W 21.89' Road Sign Post
- S 65° W 133.55' 8" Elm (Fd. Tag #31591)
- N 75° E 148.40' Power Pole (Fd. Tag #31591)
- N 10° W 189.72' Set Filed Notch in Easterly Corner of Angle Iron Fe. Post

Signed by

Wayne T. Lewis

Surveyor's Michigan License No.

41922

Date November 24, 1999

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99
V.P.B. Lewis



1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													