

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alpena

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-------|-------------|-------|
| 1. Public Land Survey | | T 32NR 06E | G-12 |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

REGISTERED
JAN 21 2000
SECTION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 6-01, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
1856: Josiah Knauer set post and witnessed
1893: Wm. H. Leroy found corner, set boulder, no new witnesses given
1958: MDOT Surveyor found 1" iron pipe, and witnessed
1992: E. T. Lewis, P.S., found 1/2" rod, and witnessed
1993 and 1997: Lewis & Lewis (E. T. Lewis, P.S. and W. T. Lewis, P.S.) found 1/2" rod, and witnessed
Unknown date: Alpena County Road Commission Field Notes, found 1/2" rerod, no witnesses given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" rerod in Long Rapids Rd. C/L and 8' East of Keating Rd C/L

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/14/99
W.T.L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County Cap, stamped to identify the corner, on 1/2" rerod in monument box

- Witnesses:
- N 35° E 76.73' 11" Spruce
 - N 45° E 91.50' Power Pole (Fd. Tag #22435)
 - N 50° E 49.70' Road Sign Post
 - S 70° E 111.39' Power Pole (Fd. Tag #22435)
 - N 45° W 67.46' Set Chis. "X" in West End of 18" Conc. Culv.



Signed by *Wayne T. Lewis*
Surveyor's Michigan License No. 41922

Date November 24, 1999