

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Alpena (County)	Located In	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>6E</u>	<u>M-10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S <u>25</u> T <u>32N</u> R <u>6E</u>	<u>14</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on September 15, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-10 GLO Josiah Knauer D.S.- July 1856
Set corner section post
Wit: 6" Balsam S54°E 10 links
5" White Birch N59°W 20 links

14- Wm. H. LeRoy, May 10, 1935, page 245, county survey notes set 4"X4" concrete monument for corner.

D. MacNeil RLS#19237, Liber 2, page 69, found a 4" concrete monument for corner.

Wm. H. LeRoy, May 10, 1935, page 245, county survey notes found corner and set 3" square stake

D. MacNeil RLS#19237, Liber 2, page 69, found a 4" concrete monument for the corner.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-10 Found 1/2" iron rod in concrete as witnessed by D. MacNeil.

14- Found a 1/2" iron rod in concrete fitting D. MacNeil distance to the south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 1/2" iron rod in 3" concrete monument
Wit: 5" Ash S84°W 5.43'
10" Apple S54°W 15.21'
4" Balsam S04°W 7.15'
3" Balsam S81°E 1.32'

14- 1/2" iron rod in concrete monument
Wit: 10" Poplar N73°E 95.51'
1/2" iron pipe N09°E 32.99'
7" Scotch Pine N60°W 59.61'
Center of N-S Trail East 4.00'

Signed by: _____

Carl T. Kiiskila

Date: _____

11-23-99

Surveyor's Michigan License No.: 33981

