

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Alpena Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T	<u>32N</u>	R	<u>6E</u>	<u>M-11</u>
	T	<u>32N</u>	R	<u>6E</u>	<u>L-11</u>
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on September 15, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		6			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11 GLO-Josiah Knauer D.S. - July 1856  
 Set cedar post of sections 25 and 36.  
 Wit: 14" Hemlock S61°W 48 links  
 10" Hemlock N-W 22 links

Wm. H. LeRoy, May 10, 1935, page 245, county survey notes found corner with crockery around stake.

D. MacNeil RLS#19237, liber 2, page 69, shows corner no witnesses or description of corner given.

L-11 GLO Josiah Knauer D.S.- July 1856  
 Set quarter section post  
 Wit: 12" Beech S24°W 29 links  
 8" Beech N57.5°E 37 links

Wm. H. LeRoy, September 1891, Page 242, county survey notes found original 1/4 stake, plain, set 3" square stake.

Joesph W. McNeil RLS#580, September 1904, Found stake with large stone on top and remains of both original bearing trees. Set new cedar stake and placed large stone same as before.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-11 Found 1 1/4" iron pipe fitting Duane MacNeil's distance North.

L-11 Found 1 1/4" iron pipe fitting Joesph McNeil's and Wm. H. Leroy distances well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 1 1/4" iron pipe  
 Wit: 28" Maple S80°W 33.50'  
 4" Ash S51°E 29.63'  
 5" Ash N82°E 29.08'  
 3" Elm N23°W 55.25'  
 Centerline of N-S Road East 4'

L-11 1 1/4" iron pipe  
 Wit: Utility Pole N76°W 50.31'  
 24" Twin Maple S80°E 43.40'  
 6" White Pine N64°E 53.03'  
 14" Twin Maple S51°W 88.95'  
 Centerline of N-S road East 9'

Signed by: \_\_\_\_\_

*Carl T. Kiiskila*

Date: \_\_\_\_\_

11-23-99

Surveyor's Michigan License No.: \_\_\_\_\_

33981

