

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Alpena _____ (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 25 T 32N R 6E	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on September 15, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

11-This corner position was not established during the original government survey.

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

11- Established the southeast corner of the northwest quarter of the southwest quarter of section 25 per standard BLM instructions for subdivision of a section.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 11-Set 5/8 X32 rerod with PS cap #33981
- |                               |       |        |
|-------------------------------|-------|--------|
| Wit: 20" Twin Maple           | North | 54.57' |
| 3-5" Maple clump              | N30°W | 73.27' |
| 12" Maple                     | South | 95.92' |
| Fence post east side of drive | S76°W | 57.19' |
| Centerline of E-W road        | South | 1'     |
| Carsonite post                | North | 33'    |



Signed by: Carl T. Kiiskila

Surveyor's Michigan License No.: 33981

Date: 11-23-99