

JAN 25 2001

2000 ALPENA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Alpena
(County)

Located In:

Corner Code #



L- 2 P- 297
08/02/2000 10:05
Page: 1 of 1
Kathy J. Matash, Register Alpena Co., MI LDC 9.00

- 1. Public Land Survey T32N R 7E C-7
T R Maple Ridge Twp.
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

I, Thomas L. Fabis, in a field survey on March 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Resurvey Josiah Knauer set post & referenced: Y. Birch 15 N30 1/2 W 22, Hem 11 S19 1/2 E 37.
- 1918: County Survey Wm. H. LeRoy Cedar stake 3" sq.
- 1980: Survey Liber 2 Page 40 Duane R. MacNeill found 6"x6" sq. conc. mon.
- 1980: R.S.Scott Survey W.O.4-6082 David B. Guthrie exis. conc. mon. & referenced.
- 1990: Survey W.O.4-993 Earl T. Lewis exis. conc. mon. & referenced.
- 1996: Survey W.O.4-2729-S Earl T. Lewis exis. conc. mon. & referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 2000: Found 6" x 6" sq. Conc. Mon. 3' South of centerline gravel rd. (LaComb Rd.). Found 3 existing witnesses indicating that this is the same corner used by MacNeill, Guthrie and Lewis. Brass Tag in P. Pole N50W 62.24, Tag #27452 in 12" Aspen S45E 56.79, 1/2" rerod #27452 NORTH 33.00

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2000: Set 3" dia. alum. cap, stamped to identify the corner, over the existing concrete monument. Witnesses are:
Brass Tag in P. Pole N50W 62.24
Tag #27452 in 12" Aspen S45E 56.79
1/2" rerod #27452 North 33.00
Center of Gate post N60W 30.99
Set Tag #31591 in 11" Maple S33E 62.54

P.A. 345 ALPENA COUNTY
PEER APPROVED 7-5-2000
DD B. L.

Signed by Thomas L. Fabis

Date July 31, 2000

Surveyor's Michigan License No. 31591

