

SURVEY & REMONUMENTATION

JAN 25 2001

2000 ALPENA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Alpena
(County)

Located In:

Corner Code #



L- 2 P- 296
08/02/2000 10:05
Page: 1 of 1
Kathy J. Matash, Register Alpena Co., MI LDC 9.00

- 1. Public Land Survey T32N R 7E F-3
T ___ R ___ Maple Ridge Twp.
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Thomas L. Fabis, in a field survey on May 5, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3						●							
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Resurvey Josiah Knauer set post & referenced: Hemlock 20 S36W 40 lks, Hemlock 16 N12W 28 lks.
- 1894: County Survey Wm. H. LeRoy found cedar stake 3" sq. & referenced.
- 1981 & 1988: R.S.Scott Surveys David Guthrie found 3/4" T-Iron & referenced.
- 1990: Survey W.O.4-1015 Earl T. Lewis existing pipe & referenced.
- 1994: Hendrick's Mortgage Report by Thomas L. Fabis 1/2" iron rod.
- 1998: Survey W.O.205-98 Ronald Bischer "T" Iron & referenced.
- 1999: Alpena Co. Rd. Comm. Corner Records Gary St. Charles found T Iron & referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 2000: Found 60 penny nail over "T" Iron 2.5 feet North of centerline of gravel road (Maple Lane). Found Bischer Tags in the following witness objects:
Fe. Post S53E 42.95
9" Apple S8E 29.48
8" Ash S20W 31.38
Found Tag #22435 in Fe. Post North 31.13

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2000: Removed 60 penny nail and set 1/2" iron rod next to existing "T" Iron and capped it with 3" dia. alum. cap stamped to identify the corner.
Existing witnesses:
Fe. Post S53E 42.95
9" Apple S8E 29.48
8" Ash S20W 31.38
Fe. Post North 31.13

P.A. 345 ALPENA COUNTY
PEER APPROVED 7-5-2000
D.J.B. Ten

Signed by Thomas L. Fabis Date July 31, 2000

Surveyor's Michigan License No. 31591

