

JAN 25 2001

2000 ALPENA COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena
(County)

Located in:

Corner Code #



L-2 P-299
08/02/2000 10:05
Page: 1 of 1
Kathy J. Matash, Register Alpena Co., MI LDC 9.00

- | | | |
|------------------------------------|--|------------------|
| 1. Public Land Survey | T <u>32</u> N R <u>7</u> E | G-6 |
| | T <u> </u> R <u> </u> | Maple Ridge Twp. |
| | T <u> </u> R <u> </u> | _____ |
| | T <u> </u> R <u> </u> | _____ |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | _____ |
| | S <u> </u> T <u> </u> R <u> </u> | _____ |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | _____ |
| | S <u> </u> T <u> </u> R <u> </u> | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas L. Fabis, in a field survey on May 24, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Resurvey Josiah Knauer set post & referenced: Hemlock 14 N85½W 15 lks, Y. Birch 7 S76E 26 lks.
- 1897: County Survey Fred A. Rice stake previously existing.
- 1906: County Survey J.W. McNeil in road bed previously set by Fred A. Rice.
- 1913: County Survey Jos. McNeil set large new stake flush with road bed.
- 1996: Survey W.O.4-2783-S Earl T. Lewis set 1/2" Rerod w/cap & referenced.
- 1997: R.S.Scott Survey W.O.4-9766 David B. Guthrie existing 1/2" iron rod.
- 1998: Fabis Survey W.O.97361-1 Thomas L. Fabis exis. 1/2" iron rod w/cap & referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 2000: Found capped rerod 1' East of gravel road centerline and the following existing witnesses indicating that this is the same corner used by Lewis and Guthrie: Fe. Post S85E 27.36, 4" Apple S85W 40.54, 4" Birch N50E 28.02.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2000: Removed existing plastic cap and set 3" dia. alum. cap, stamped to identify the corner, over the existing 1/2" iron rod. Existing Lewis tags in the following witnesses:
Fe. Post S85E 27.36
4" Apple S85W 40.54
4" Birch N50E 28.02
Set tag #31591 in 5" Tam. N52E 41.07

P.A. 345 ALPENA COUNTY
PEER APPROVED 7-5-2000
DJB

Signed by Thomas L. Fabis
Surveyor's Michigan License No. 31591

Date July 31, 2000

