

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Kathy J. Patach*  
REGISTER OF DEEDS

For corners in  
Alpena County

Located In: Corner Code #

- 1. Public Land Survey T 32N R R7E G-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Earl T. Lewis, in a field survey on May 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

JUNE 10, 1856: GLO Surveyor, Josiah Knauer set post, no monumentation given, witnesses given:

W. Cedar. 12 S 65 E 9 links

W. Cedar 7 N 27 1/2 W 2 1/2 links

NOVEMBER 11, 1897: County Surveyor, Fred Rice used corner for Section 15 breakdown, no monumentation or witnesses given.

DECEMBER 20, 1904: County Surveyor, Joseph McNeil, used corner for Section 22 breakdown, no monumentation or witnesses given.

DECEMBER 18, 1913: County Surveyor, Joseph McNeil, found stake in roadbed, no monumentation or witnesses given.

1989: R.S. Scott Associates, Inc. field notes for W.O. #4-7777, found PK nail, no witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK nail in asphalt 8 feet East and 1' South of intersection of LaComb and Deitz roads.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995, Placed appropriately stamped Alpena County Remonumentation aluminum cap on 1/2" x 24" rerod in monument box, which was set in place of existing PK nail.

Witnesses:

- N 55° W 85.60' Power Pole (found tag)
- N 40° W 119.70' Southeast Corner of Maple Ridge Township Hall
- N 55° E 64.36' Power Pole
- S 25° E 148.90' 10" Poplar

P.A. 345 ALPENA COUNTY  
PEER APPROVED 10/29/95  
*D. B. Lane*



Signed by Earl T. Lewis Date October 8, 1995

Surveyor's Michigan License No. 27452