

RECORDED
ALPENa COUNTY MI.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 12 2 12 PM '95

Kathy M. Patach
REGISTER OF DEEDS

For corners in
Alpena County
(County)

Located In: Corner Code #

- 1. Public Land Survey T 32N R 07E G-8
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Earl T. Lewis, in a field survey on May 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

JUNE 24, 1856: GLO Surveyor, Josiah Knauer set post, no monumentation given, witnesses given:

- W. Cedar. 7 N 40 W 18 links
- Cedar 6 S 40 E 22 links

DECEMBER 20, 1904: County Surveyor, Joseph McNeil, used corner for Section 20 breakdown, set cedar stake in place of old one witnesses given:

- W. Cedar. 7 N 40 W 18 links
- Cedar 6 S 40 E 22 links

1989: R.S. Scott Associates, Inc. field notes for W.O. #4-7777, found 1/2" rod, no witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rered in centerline of Deitz Road.

SURVEY &
REMONUMENTATION

JUL 30 1999

SECTION

P.A. 345 ALPENa COUNTY
PEER APPROVED 6/29/95
D. B. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995, Placed appropriately stamped Alpena County Remonumentation aluminum cap on existing 1/2" rered, 6" below road surface.

Witnesses:

- N 45° W 53.00' 12" Spruce
- S 50° W 44.45' 5" Cedar
- S 85° E 41.35' 8" Cedar
- N 70° E 46.75' 5" Cedar



Signed by Earl T. Lewis

Date October 8, 1995

Surveyor's Michigan License No. 27452