

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Oct 12 2 12 PM '95

Kathryn Matash REGISTER OF DEEDS

005755

Register of Deeds Stamp & File Number

For corners in Alpena County

Table with columns: Located In, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a central dot at row 9, column G.

I, Earl T. Lewis, in a field survey on May 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: JUNE 24, 1856: GLO Surveyor, Josiah Knauer set post, no monumentation given, witnesses given: Hemlock 8 N 73 E 21 links Cedar 6 S 77 W 23 links APRIL 10, 1893: County Surveyor, Fred Rice, used corner for road survey, found stake, no witnesses given. DECEMBER 20, 1904: County Surveyor, Joseph McNeil, used corner for Section 22 breakdown, set cedar stake in place of old one no witnesses given. 1989: R.S. Scott Associates, Inc. field notes for W.O. #4-7777, set PK nail 33 feet off fence, no witnesses given. MAY 14, 1994: Thomas L. Fabis P.S. field notes, set 1/2" rod over 1" iron pipe, also found PK nail in intersection of Deitz and Irwin roads, no witnesses given. B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 1/2" rerod 10.7' North and 2.8' East of intersection of Deitz and Irwin roads.

SURVEY & REMONUMENTATION

JUL 30 1999

SECTION

P.A. 345 ALPENA COUNTY PEER APPROVED 6/24/95 [Signature]

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 1995, Placed appropriately stamped Alpena County Remonumentation aluminum cap on existing 1/2" x 24" rerod, over existing 1" pipe, 2" below the road surface (in monument box).

- Witnesses: S 35° E 56.10' Power Pole S 40° W 56.87' Power Pole West 73.53' 8" Poplar N 75° W 64.85' Telephone Pole



Signed by Earl T. Lewis Date October 8, 1995 Surveyor's Michigan License No. 27452