

JAN 25 2001

2000 ALPENA COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena  
(County)

Located in:

Corner Code #



L- 2 P- 292  
08/02/2000 10:05  
Page: 1 of 1  
Kathy J. Matash, Register Alpena Co., MI LDC 9.00

- 1. Public Land Survey      T32N R 7E      H-3  
   T      R      Maple Ridge Twp.  
   T      R      \_\_\_\_\_  
   T      R      \_\_\_\_\_
- 2. Property Controlling      S      T      R      \_\_\_\_\_  
   in Section                    S      T      R      \_\_\_\_\_
- 3. Miscellaneous            S      T      R      \_\_\_\_\_  
   Property in Sec.            S      T      R      \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Thomas L. Fabis, in a field survey on May 24, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2		1	
3								●					
4	7		8		9			10		11		12	
5													
6	18		17		16			15		14		13	
7													
8	19		20		21			22		23		24	
9													
10	30		29		28			27		26		25	
11													
12	31		32		33			34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1855: G.L.O. Resurvey Josiah Knauer set post & referenced: Cedar 11 N17W 29 links, Cedar 10 S77E 9 links.
  - 1893: County Survey Fred A. Rice visits corner.
  - 1970's: County Rd. Comm. Corner Records Gary St. Charles 1/2" rerod & referenced.
  - 1982: L.C.R.C. Liber 1 Page 153 & Porter's Witness Records Ronald Bischer 1/2" rod and referenced.
  - 1990: Survey W.0.4-1010 Earl T. Lewis existing 1/2" rod & referenced.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 2000: Found 1/2" iron rod bent over on top of wood stake 4.5 feet North of centerline of gravel road, old fences going North and South. Found one existing witness: Old shiner in Fe. Post N47E 49.33

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 2000: Removed existing bent re-rod and set 1/2" iron rod with 3" dia. alum. cap, stamped to identify the corner, in center of existing wood stake.

Witnesses are:

- Old shiner in Fe. Post N47E 49.33
- Tag #31591 in Cor. Fe. Post South 33.19
- Tag #31591 in 5" Apple in Clump N10W 50.11
- Tag #31591 in Fe. Post S37E 45.97

P.A. 345 ALPENA COUNTY  
PEER APPROVED 7-5-2000  
*D.D.B. to*

Signed by Thomas L. Fabis

Date July 31, 2000

Surveyor's Michigan License No. 31591

