

**SURVEY &
REMONUMENTATION**

NOV 16 1998

P.A. 345 ALPENA COUNTY 1998 ALPENA COUNTY REMONUMENTATION CORNER

PEER APPROVED 8/14/98
D.P. Fabis

**SECTION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

Liber **00002** Page **0152**

STATE OF MICHIGAN
County of Alpena
Recorded
08-20-1998 09:19:27
Kathe J. Matash
REGISTER OF DEEDS

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32NR 7E</u>	I-2
	T ___ R ___	Maple Ridge Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas L. Fabis, in a field survey on Feb. 19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1857: G.L.O. Survey Josiah Knauer - Set post & referenced: Cedar 12 N67E 20, Cedar 18 S82W 11:
- 1893: County Survey Fred Rice - Found witness trees standing.
- 1981: Survey Liber 1 Page 988 & 989 Earl Lewis - Set 1/2" Rod & referenced.
- 1982: L.C.R.C. Liber 1 Page 155 Ron Bischer - Found 1/2" Rod & referenced.
- 1990: Survey W.O.4-1039 Earl Lewis - Found 1/2" Rod & referenced.
- 1992: Mortgage Inspection W.O.4-8499 R.S.Scott Associates, Inc. - Found 1/2" Rod.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998: Found 1/2" iron rod 4 feet West of centerline of Cathro Rd. (gravel surface) Intersecting fences East & West. Also, found 2 witness objects by Ron Bischer and 2 witness objects by Earl Lewis, indicating that this is the same corner that they used.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1998: Set 3" dia. aluminum cap, stamped to identify the corner, over the existing 1/2" iron rod.
- Reestablished witnesses are:
Set tag #31591 in the following witness objects:
Power Pole N25E 59.27'
4" Apple N80E 39.72'
7" Cedar East 57.00'
Fence Post West 27.02'



Signed by *Thomas L. Fabis*
Surveyor's Michigan License No. 31591

Date August 14, 1998