

**SURVEY &
REMONUMENTATION**

NOV 16 1998

P.A. 345 ALPENA COUNTY
PEER APPROVED 8/10/98
Del B. C...

1998 ALPENA COUNTY REMONUMENTATION CORNER
SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

00002 Page 0154

STATE OF MICHIGAN
County of Alpena
Recorded
08-20-1998 09:19:42
Kathy J. Matash
REGISTER OF DEEDS

For corners in

<u>Alpena</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>32NR 7E</u>	<u>I-4</u>
	T <u> </u> R <u> </u>	<u>Maple Ridge Twp.</u>
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas L. Fabis, in a field survey on Feb. 19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10	●	11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
1857: G.L.O. Survey Josiah Knauer Set Post & referenced: Sugar 6 S46E 28, Elm 7 S89W 26.
1980: Survey Liber 1 Page 964 Duane MacNeill Set Railroad Spike & witnessed.
1984: Survey Liber 2 Page 328 Duane MacNeill Found Railroad Spike & witnessed.
1996: Survey W.O. 0402789A Lewis & Lewis Reset 1/2" rerod per D.R. MacNeill & witnessed.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1998: Found 1/2" iron rod P.S. #27452 2.5 feet East of centerline of Cathro Rd. (gravel surface) intersecting fences East & West. Also, found five existing witnesses: S75W 29.78' Old disk in Anchor Pole, N85W 35.02' 6" Apple tag 27452, S85E 31.46' 6" Apple tag 27452, S75E 34.01' 5" Apple tag 27452, Due West 28.04' Old disk in Fe. Post.

The position of this corner is compatible with the local surveys mentioned above and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1998: Set 3" dia. aluminum cap, stamped to identify the corner, over the existing 1/2" iron rod.

References are:
S75W 29.78' Old disk in Anchor Pole
N85W 35.02' 6" Apple tag 27452
S85E 31.46' 6" Apple tag 27452
S75E 34.01' 5" Apple tag 27452
Due West 28.04' Old disk in Fe. Post

Signed by Thomas L. Fabis
Surveyor's Michigan License No. 31591

Date August 14, 1998

