

NOV 16 1998

P.A. 345 ALPENA COUNTY

PEER APPROVED: 8/10/98

Daniel T. Kibbe

1998 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION 00002 Page 0143

For corners in

<u>Alpena</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>7E</u>	<u>J-3</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
County of Alpena
Recorded
08-20-1998 09:18:04
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3									●			
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Daniel T. Kibbe, in a field survey on March 17, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1857: GLO Survey by Josiah Knaver-set quarter section post; referenced: Cedar 5-N10E-20 links/Hemlock 5-S69W-29 links
- 1892: County Survey by William H. LeRoy and by Jos. W. McNeil (Deputy Surveyor)-Old stake cedar 2" sq; referenced: Cedar 5-N10E-20 ONBT
- 1893: County Survey by Fred A. Rice-ran to quarter post
- 1981: Survey by Earl T. Lewis recorded in Liber1 page 938-existing 3/4" Pipe; referenced: 7" Basswood-S50E-52.00' 12" Basswood-South-51.03'/16" Maple-N40W-36.5'
- 1997: Survey by Wayne T. Lewis-existing pipe leaning SW'ly. Set 1/2" rebar @ base of pipe; referenced: 24" Maple-N25W-37.40' 8" Maple-N08E-40.72'/10" Twin Maple-S50E-51.40'/6" Maple-S45W-52.68'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998: Remon. Survey by Daniel T. Kibbe-found bar & cap (WTL) next to 3/4" pipe laying down. 1' South CL road. Old fence row North & South (treeline & rock row) .5 below surface

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1998: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod.
Referenced:
Found WTL tag in 8" Ash-S52E-51.43'
Set tag over tack in 13" Basswood-S14W-51.31'
Found WTL tag in 8" Maple-N10E-40.63'
Found WTL tag in 20" Maple-N30W-37.40'



Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278

Date August 14, 1998