

NOV 16 1998

P.A. 345 ALPENA COUNTY  
PEER APPROVED 8/14/98  
*Det. B. Lane*

1998 Alpena County Remonumentation Corner  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION  
00002 Page 0145

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>7E</u>	<u>L-3</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
County of Alpena  
Recorded  
08-20-1998 09:18:21  
Kathy J. Matash  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Daniel T. Kibbe, in a field survey on March 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2			1	
3													
4	7		8		9		10		11			12	
5													
6	18		17		16		15		14			13	
7													
8	19		20		21		22		23			24	
9													
10	30		29		28		27		26			25	
11													
12	31		32		33		34		35			36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1857: GLO Survey by Josiah Knaver-set quarter section post; referenced: Cedar 8-N39W-17 links/Beech 14-S24E-26 links
- 1892: County Survey by William H. LeRoy-reestablished old 1/4 corner. Set new cedar stake 3" sq.; referenced: Beech 18-S24E-26 ONBT/Cedar 12-N61W-16 (down) ONBT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998: Remon. Survey by Daniel T. Kibbe-found 3" PK nail 8" below surface. 4' South CL of road. 1.8' East of fence to North. On fence line to the South. Set rebar in place of PK.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1998: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod. Referenced:  
Set tag in 12" Poplar-S31E-32.64'  
Set tag in 8' Cedar cluster-S63W-57.68'  
Set tag in fence post-N30W-37.77'  
Set tag in 6" Red pine-N38E-67.59'



Signed by *Daniel T. Kibbe*  
Surveyor's Michigan License No. 37278

Date August 14, 1998