

SURVEY & REMONUMENTATION

DEC 03 1993

005686

1993 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
ALPEN A COUNTY MI.
LIBER 1 PAGE 253
SEP 10 9 39 AM '93

Myron A. Johnston
REGISTER OF DEEDS

For corners in

Alpena (County)	Located in:	Corner Code ##
1. Public Land Survey	T 32N R 8E	B-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

(David B. Guthrie, in a field survey on July 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. re-survey by Josiah Knauer - Set post and referenced: Beech 7 - N70W - 17 / Cedar 8 - S65W - 6
- 1889: County survey by Wm. H. LeRoy - Found G.L.O corner and original N.B.T.'s: Beech 12 - N70W - 17 / Cedar Stump 8 - S65W - 6 / Y. Birch Stump 20 - N24E - 58½.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Set ½" x 24" iron rod at the intersection of a wood and stone fence east and west and old fenceline south. The location of this corner is compatible with former County Surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Set ½" x 24" iron rod with 3" aluminum cap stamped to identify the corner. Referenced:
 S74°W - 5" Spruce - 16.85 feet
 S09°E - 6" Ash - 10.79 feet
 N17°E - 7" Maple - 16.51 feet
 N08°W - 4" Aspen - 25.73 feet



Signed by *David B. Guthrie*
 Surveyor's Michigan License No. 22435

Date 9/10/93