

DEC 10 1993

LIBER

1 PAGE 277

007741

1993 ~~Alpena~~ ^{Alpena} County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED ALPENA COUNTY MI.

DEC 7 9 21 AM '93

Spencer A. Johnston
REGISTER OF DEEDS

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>8E</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Daniel T. Kibbe, in a field survey on July 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Re-survey by Josiah Knauer - set post and referenced: Cedar 11 - N37W - 10 / W. Birch 7 - S58 3/4E - 10.
- 1890: County survey by Wm. H. LeRoy - Found old stake.
- 1978: Survey by Duane MacNeill - set 1" pipe and referenced.
- 1985: Survey by Earl T. Lewis - Found 1" pipe and referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found 1" pipe with Duane MacNeill cap on an old E-W fence line ⁺ and 25' West of an old fence line North. This corner was set by Duane MacNeill in 1978 by single proportionate method. The position is quite compatible with an 1890 county survey by Wm. LeRoy. It is a reference for local surveys. After a thorough search, it is believed that the best evidence is the found pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set 1/2" x 18" iron rod with 3" aluminum cap stamped to identify the corner.
- Referenced:
 - S85°E - 12" dead Aspen - 34.62 feet
 - S72°W - 7" Aspen - 14.43 feet
 - North - 8" Cedar - 19.90 feet
 - N88°E - 11" Ash - 38.10 feet
 - S55°E - 5" Ash - 4.60 feet



Signed by *Daniel T. Kibbe*

Date November 24, 1993

Surveyor's Michigan License No. 37278