

**SURVEY &  
REMONUMENTATION**

DEC 03 1993

1993 Alpena County Remonumentation Corner

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

005689

RECORDED  
ALPENA COUNTY MI.

LIBER 1 PAGE 256  
SEP 10 9 39 AM '93

*Myung A. Johnston*  
REGISTER OF DEEDS

For corners in

Alpena

(County)

Located In:

Corner Code #

- |                                       |   |            |   |           |            |
|---------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey                 | T | <u>32N</u> | R | <u>8E</u> | <u>D-7</u> |
|                                       | T | _____      | R | _____     | _____      |
|                                       | T | _____      | R | _____     | _____      |
|                                       | T | _____      | R | _____     | _____      |
| 2. Property Controlling<br>in Section | S | _____      | T | _____     | R          |
|                                       | S | _____      | T | _____     | R          |
| 3. Miscellaneous<br>Property in Sec.  | S | _____      | T | _____     | R          |
|                                       | S | _____      | T | _____     | R          |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David B. Guthrie, in a field survey on July 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1855: G.L.O re-survey by Josiah Knauer - Set post and referenced: Sugar 6 - N4W - 18 / Sugar 14 - S30W - 26.
- 1888: County survey by Fred A. Rice - Found corner set by G.L.O. survey.
- 1976: Survey by David B. Guthrie - Found 1/2" iron rod and referenced.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1993: Found 1/2" iron rod which has been used for local surveys. The location of this corner is compatible with former county surveys which were completed approximately 30 years after the G.L.O. survey. This corner lies in the Center of LaComb Road in line with a Boundary Line Fence South.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1993: Set 1/2" x 24" iron rod with a 3" aluminum cap stamped to identify the corner. Referenced:
  - S10°W - Utility Pole - 36.24 feet
  - N15°E - 10" Cedar - 68.65 feet
  - S35°W - 8" Tamarack - 56.19 feet
  - N42°W - 10" Balm of Gilead - 61.52 feet



Signed by *David B. Guthrie* Date 9/10/93

Surveyor's Michigan License No. 22435