

DEC 03 1993

005687

COMMISSION  
1993 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
ALPENA COUNTY MI.

LIBER SEP 10 1 9 39 AM '93 PAGE 254

*Myriam A. Johnston*  
REGISTER OF DEEDS

For corners in

Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey

T 32N R 8E

E-8

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Guthrie, in a field survey on July 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O Re-survey by Josiah Knauer - set post and referenced: Beech 16 - S55°W - 4 / Beech 9 - N69°E - 24½.
- 1888: County survey by Fred A. Rice - Found G.L.O Corner, no references.
- 1977: Survey by David B. Guthrie - Found ½" iron rod and referenced.
- 1981: Survey by Duane MacNeill - No references or type of marker - Liber 2, page 30.
- 1989: Survey by Gary St.Charles - Found ½" iron rod and referenced. L.C.R.C. Liber 1, page 201.
- 1991: Survey by David B. Guthrie - Found ½" iron rod in Monument Box - verified prior references.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found ½" iron rod in Monument Box. This corner has been used for local surveys. The corner lies in the center of French Road in line with Fence Boundary Lines east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set ½" x 24" iron rod with a 3" aluminum cap stamped to identify the corner. Referenced:
  - N68°E - Utility Pole - 56.58 feet
  - S62°E - 8" Twin Maple - 65.45 feet
  - S30°E - 5" Spruce - 95.25 feet
  - N82°W - 6" Maple - 67.50 feet



Signed by *David B. Guthrie*

Date 9/10/93

Surveyor's Michigan License No. 22435