

DEC 03 1993

005683

RECORDED ALPENA COUNTY MI. LIBER 1 PAGE 250 SEP 10 9 38 AM '93

COMMISSION 1993 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS

For corners in

Alpena

(County)

Located In:

Corner Code ##

Table with 3 columns: Description, Township/Range, Corner Code. Row 1: Public Land Survey, T 32N R 8E, E-9. Row 2: Property Controlling in Section, S T R. Row 3: Miscellaneous Property in Sec., S T R.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column G and row 9.

I, David B. Guthrie, in a field survey on July 12, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O Re-survey by Josiah Knauer - Set post and referenced: Cedar 14 - S34 1/2 E - 26 / Cedar 12 - N73 1/2 E - 22
1888: County survey by Fred A. Rice - Found G.L.O Corner
1977: Survey by David B. Guthrie - Found 1/2" iron rod and referenced.
1989: Survey by Gary W. St.Charles - Found 1/2" iron rod, referenced and recorded. L.C.R.C., Liber 1, page 202.
1991: Survey by David B. Guthrie - Found 1/2" iron rod in Monument Box, verified references.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found 1/2" iron rod in Monument Box. This corner is a reference for local surveys and lies in a road intersection. It is compatible with former County Surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set 1/2" x 24" iron rod with 3" aluminum cap stamped to identify the corner. Referenced: S82°E - Utility Pole - 119.00 feet S51°E - Utility pole - 74.84 feet S56°E - Utility Pole - 130.05 feet N81°E - 12" Apple - 114.42 feet



Signed by [Signature]

Date 9/10/93

Surveyor's Michigan License No. 22435