

DEC 10 1993

LIBER

1 PAGE 272

007736

COMMISSION

1993 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED ALPENA COUNTY MI.

DEC 7 9 20 AM '93

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Alpena (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>8E</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel T. Kibbe, in a field survey on July 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Re-survey by Josiah Knauer - set post and referenced: Hemlock 18 - S69 1/2W - 12 / Sugar 8 - N61 1/2E - 19.
- 1977: Survey by Duane MacNeill - referenced.
- 1978: Survey by Duane MacNeill - set 1/2" rerod with cap and referenced.
- 1979: Survey by Duane MacNeill - referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Set 1/2" rebar from 1979 Duane MacNeill witnesses obtained from a survey recorded in liber 1 pg 973. Corner falls 1' South of the Center of a winding trail road. MacNeill set this corner in 1978 from a combination of prorations and found evidence in Sec. 9 from the 1918 plat of Lakeside Rod & Gun Club. This corner is compatible with 1855 G.L.O. survey and is a reference for local surveys. This corner appears to be the best evidence of the true position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Set 1/2" x 18" iron rod with 3" aluminum cap stamped to identify the corner.
Referenced:
 S45°W - 5" White Birch - 24.68 feet
 North - 10" Aspen - 18.93 feet
 S70°E - 5" Ash - 22.64 feet
 S80°W - 5" Ash - 35.90 feet



Signed by Daniel T. Kibbe

Date November 24, 1993

Surveyor's Michigan License No. 37278