

DEC 10 1993

007740

1993 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED ALPENA COUNTY MI.

DEC 7 9 21 AM '93

Register of Deeds Stamp & File Number

For corners in

Alpena (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>8E</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on July 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Re-survey by Josiah Knauer - set post and referenced: Cedar 7 - N57 1/2E - 6 / Cedar 14 - S2 1/4W - 17.
- 1887: County survey by Fred A. Rice - Found G.L.O. corner and referenced.
- 1977: Survey by Duane MacNeill - Set 1" pipe and referenced.
- 1981: Survey by Duane MacNeill - Found 1" pipe and referenced.
- 1993: Alpena County Road Commission- set 1/2" rebar in Monument Box after road construction.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found 1/2" rebar in Monument Box in the Center of Lacombe Road. This corner is very compatible with former county surveys. It is a reference for local surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Placed 3" aluminum cap stamped to identify the corner. Referenced:
 - S27°W - 7" Cedar - 66.70 feet
 - S02°E - 8" Birch - 57.46 feet
 - N10°W - 6" Cedar - 45.98 feet
 - N17°E - 7" Elm - 45.81 feet



Signed by Daniel T. Kibbe

Date November 24, 1993

Surveyor's Michigan License No. 37278