

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

DEC 16 10 18 AM '93

REGISTER OF DEEDS

For corners in

Alpena (County)

Located In:

Corner Code #

- 1. Public Land Survey T 32N R 8E G - 9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. A dot is marked at row 9, column G.

I, Duane R. MacNeill, in a field survey on July 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1855 - Cedar Post

Witnesses:

- Sugar 14 S 79 1/2 W 28
Do 20 N 65 1/2 E 16

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - February - Corner reset by Tom Fabis #31591 using combined evidence of old fences, G.L.O. notes and early 20th Century County Surveyor's notes. Set 1/2" Rerod Cap #31591

Witnesses:

- N 25° W 18.73' 9" Maple
N 22° E 26.25' 11" Ash
S 54° W 12.15' 7" Maple
S 20° E 36.54' 10" Ash

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" Rerod with cap as set by Fabis. Replaced plastic cap on Rerod with Alpena County Remonumentation Aluminum Cap, appropriately stamped.

Witnesses:

- N 12° W 18.76' 10" Maple Fd.
N 36° E 26.23' 14" Ash Fd.
S 50° W 12.24' 8" Maple Fd.
S 12° E 36.58' 12" Ash Fd.

Witnesses were freshened as necessary, nails replaced with duplex nails bearing a brass washer stamped License #19237

Signed by Duane R. MacNeill
Surveyor's Michigan License No. 19237

Date December 6, 1993

