

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
ALPENA COUNTY MI.

For corners in

Alpena
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 32N R 8E I - 9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

DEC 16 10 19 AM '93

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on July 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column I and row 9.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1855 - Cedar Post

1901 - Reported by County Surveyor Leroy as being "Well Established"

1939 - 6x6 Concrete monument set by County Surveyor McNeil. No witnesses record

Witnesses:

Hemlock 12 S 48 W 26
Cedar 9 N 77 1/2 E 5

Witnesses:

Cedar fence Post 8 S 44 E 54 1/2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 6x6 concrete monument East of the Center line of Long Lake Road. Witness tags found surrounding location. Monument has been referenced upon several recorded surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument lowered to approx. 9" below road surface. Appropriately stamped Alpena County Remonumentation Aluminum Cap secured on rerod in center of monument.

Witnesses:

N 60° E 36.01' Power Pole Fd.
N 82° W 34.31' Power Pole Fd.
S 66° W 40.24' Tel. Pole Fd.
S 16° E 51.40' 12" Maple Set

Witnesses were freshened as necessary, and nails replaced with duplex nails bearing a brass washer stamped License # 19237

Signed by

[Signature]

Date December 6, 1993

Surveyor's Michigan License No. 19237

