

MAY 18 1997 1996 ALPENA COUNTY REMONUMENTATION CORNER

COMMISSIONER LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 50

For corners in Alpena Located In: Corner Code #
(County)

- 1. Public Land Survey T 32N R 8E L-11 (N¹, 36) ✓
T _____ R _____ Alpena Twp.
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

RECORDED
ALPENA COUNTY MI.

JUL 22 11 07 AM '96

Harry J. Pridash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas L. Fabis, in a field survey on May 29, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Resurvey by Josiah Knauer - Set post & referenced: (Cedar 6 - S54E - 9, Cedar 5 - N27W - 21).
- 1970: Survey (W.O. 4-3939) by James Scott of R.S. Scott Engineering Co. - Existing Iron and witnessed to Existing iron 33' North.
- 1978: Recorded Survey (Liber 1 Page 890) by Duane MacNeill - Set 1" Pipe in a different location and referenced.
- 1979: L.C.R.C. (Liber 1 Page 109) and survey (W.O. 4-5844) by David Guthrie of R.S. Scott Associates - Found Railroad Spike and referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Found 1" iron bar in position of Railroad Spike and the 3 existing witnesses as mentioned in Guthrie's L.C.R.C. and survey. Also found cedar stake next to 1" iron bar.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 7/17/96
Paul A. Carter

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Removed 1" Bar and set 3" dia. aluminum cap, stamped to identify the corner, over a 1/2" iron rod next to existing cedar stake.

References:

- 6" Spruce - S30W - 65.71'
- 8" Cedar - S50W - 74.74'
- 12" W.Pine - N55W - 34.25'
- 9" Spruce - N20E - 37.98'



Signed by Thomas L. Fabis

Date July 17, 1996

Surveyor's Michigan License No. 31591