

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
Alpena	Located In	Corner Code #	
(County)			
1. Public Land Survey	T <u>32N</u> R <u>8E</u>	<u>M-7</u>	
	T <u>32N</u> R <u>8E</u>	<u>L-7</u>	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Carl T. Kiiskila, in a field survey on January 19, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7 G.L.O. John Hodgson, D.S. 1840 set post for corner 13 and 24 Wit: 14" Cedar S31°W 8 links 8" B. Ash N47°W 14 links	L-7 G.L.O. Josiah Knauer D.S. 1856 set quarter section post Wit: 10" Hemlock S51°E 8 links 5" Hemlock N15°W 7 links
Josiah Knauer 1856 hit post Wit: 5" Cedar S71°W 12 links 5" W. Ash N46°W 12 links	Pages 121 and 122 County Survey Notes December 1909 Joseph W. McNeil found one quarter corner set by F.A. Rice.

Pages 121 and 122 County Survey Notes December 1909
Joseph W. McNeil found corner in range line at cross roads.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-7 Found 1/2" iron rod in a 1/2" iron pipe fitting J.W. Knauer distance west.	L-7 Found 3/4" pipe fitting J.W. McNeil's distances East and West.
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Set 5/8" X 16" rerod with cap Wit: *Shiner in power pole S57°W 44.14' *Shiner in 6" Cedar S38°E 58.05' 5" Tamarack N41°W 66.79' 5" Ash N62°E 53.53' Fd. 1/2" iron bar N64°E 3.99'	L-7 Found 3/4" iron pipe Wit: 5" Spruce N36°E 21.52' 4" Tamarack N33°W 31.26' 3" Cedar S32°W 47.72' 3" Balsam South 46.12'
--	--

* Old witnesses by others

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 12-10-03

