

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Alpena Located In _____ Corner Code # _____
 (County)

1. Public Land Survey		T	<u>32N</u>	R	<u>8E</u>	<u>L-3</u>
		T	<u>32N</u>	R	<u>8E</u>	<u>M-3</u>
2. Property Controlling in Section	S	T	_____	R	_____	_____
	S	T	_____	R	_____	_____
3. Miscellaneous Property in Section	S	T	_____	R	_____	_____
	S	T	_____	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on January 19, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3												●	●
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-3 GLO- John Hodgson, D.S., April 1840.
 Set quarter section post
 Wit: Hemlock 8 N61°E 3.5 links
 Cedar 14 N16°W 17 links

M-3 GLO- John Hodgson, D.S., 1840.
 Set post corner section 1 and 12.
 Wit: Beech 8 N50°W 10 links
 Beech 8 S44°E 10 links

R.S. Scott Engineering unrecorded certificate of survey
 September 1975 tied to corner.

January 1982 Consumers Power Co. Found a square wood post for the Northwest corner of section 7, T.32N.,R.9E.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L-3 Re-established the North quarter of section 12 from information provided by R.S. Scott Engineering.

M-3 Found a 1/2" rod with Glenn A. Fauser P.S. Cap #18657 fitting his distances South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Set 1"X 36" Iron pipe with PS cap #33981
 Wit: 3" Basswood N55°E 20.18'
 12" Maple S77°E 37.19'
 7" Twin Maple S24°E 31.61'
 12" Maple S25°W 9.37'
 Centerline of power line East 130' ±

M-3 1/2" capped rerod in stone mound and square post
 Wit: 12" Cedar N86°E 56.76'
 3" Balsam S26°E 16.04'
 18" Cedar S22°W 35.89'
 6" Twin Maple N31°E 73.06'

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 12-10-03

