

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Alpena Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S 12 T 32N R 8E 9  
 S 12 T 32N R 8E 6

3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on, October 7, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

9- September 1975 R.S. Scott Engineering unrecorded certificate of survey shows they set a 1/2" iron for the Southeast corner of the Southwest quarter of the Northeast quarter of section 12.

6- September 1975 R.S. Scott Engineering unrecorded certificate of survey shows they set a concrete monument for the Northeast corner of the Southwest quarter of the Northeast quarter of section 12.

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

9- Re-Established the Southeast corner of the Southwest quarter of the Northeast quarter of section 12 from information provided by R.S. Scott Engineering.

6- Found a concrete monument as set by R.S. Scott Engineering.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

9- Set 5/8" X16" capped iron rod with P.S. Cap #33981  
 Wit: 6" Beech S55°W 45.92'  
 6" twin Maple N18°W 45.31'  
 Conc. Monument N06°E 33.12'  
 12" Beech S19°E 63.25'  
 Blue Carsonite Post North 33.4'±

6- Found Conc. Monument  
 Wit: 18" Beech N86°W 31.40'  
 8" Twin Basswood N12°W 9.71'  
 6" Maple N12°E 7.86'  
 10" Basswood West 1.40'  
 Blue Carsonite Post North 1'±

Signed by: \_\_\_\_\_

Carl T. Kiiskila

Date: \_\_\_\_\_

12-10-03

Surveyor's Michigan License No.: \_\_\_\_\_

33981

